

To: 1 041236 3-13  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 047-20,876-0000  
C NW SE, SEC. 16, T 25 S, R 16 W/X  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5427

Lease Name Meyer A Well # 3  
County Edwards 144.56

Operator: D.R. Lauck Oil Co., Inc.  
Name & Address 221 S. Broadway, Ste. 400  
Wichita, KS 67202

Well Total Depth 4448 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Service License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 13 Month: 3 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Service (phone) 316-587-3361

were: 5 1/2" at 4440' with 150 sx cement, Open hole 4440-4448', Perfs at 4382-90, 4334-4438'

1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 9:45 a.m. Day: 13 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 5 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2283' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE MAR 21 1997  
I hereby observe this plugging.

INV. NO. 47785  
3-13

Signed Stephen J. Pfeifer (TECHNICIAN)

3-20-97  
RECEIVED  
SAS CORP  
MAR 20 11:30 AM