

To: 1 041233 3-13
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-20,399-0000
C SE NE, SEC. 16, T 25 S, R 16 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5427
Operator: D.R. Lauck Oil Co., Inc.
Name:
Address 221 S. Broadway, Ste. 400
Wichita, KS 67202

Lease Name Meyer B Well # 3
County Edwards 142.44
Well Total Depth 4383.5 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Service License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 13 Month: 3 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D.S & W Well Service (phone) 316-587-3361

Work: 5 1/2" at 4374' w/100 sx cement, Open hole 4374-4383.5'
1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 13 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2228' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE MAR 21 1997
INV. NO. 47788

Signed Stephen J. Pfeiffer (TECHNICIAN)

3-20-98
RECEIVED
MAR 20 11 30 AM '98
STATE CORPORATION COMMISSION