

To: 1 041235 3-13
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-20,113-0000
C SW NE, SEC. 16, T. 25 S, R. 16 WXX
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5427
Operator: D.R. Lauck Oil Company, Inc.
Name: 221 S. Broadway, Ste. 400
Address: Wichita, KS 67202

Lease Name Meyer B Well # 1
County Edwards 144.17
Well Total Depth 4436 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well Input Well SMO Well O&A
Other well as hereinafter indicated

Plugging Contractor D S & W Well Service License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:15 p.m. Day: 13 - Month: 3 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Service (phone) 316-587-3361

Work: 5 1/2" at 4429' w/100 sx cement, PBTB 4405', Perfs at 4374-82, 4337-42'
1st plug sand back to 4285' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 1 p.m. Day: 13 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4285' and dumped 5 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 250 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1585' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE MAR 21 1997
OBSERVE THIS PLUGGING.

INV. NO. 47786
3-13

Signed Stephen J. Cooper (TECHNICIAN)

3-20-98
RECEIVED
MAR 20 11:30 AM
KANSAS CORP. DIV.