

To: 1 041234 3-13 API NUMBER 15- 047-20,262-0000  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION App. C NW NE, SEC. 16, T 25 S, R 16 W/8  
130 S. Market, Room 2078  
Wichita, KS 67202  
4620 feet from S section line  
1900 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5427 Lease Name Meyer B Well # 2  
Operator: D.R. Lauck Oil Co., Inc. County Edwards 143.48  
Name & Address 221 S. Broadway, Ste. 400 Well Total Depth 4415 feet  
Wichita, KS 67202 Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor D S & W Well Service License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 13 - Month: 3 - Year: 19 97  
Plugging proposal received from Kent Strube  
(company name) D S & W Well Service (phone) 316-587-3361

were: 5 1/2" at 4414' w/100 sx cement, PBD 4384', Perfs at 4364-70'  
1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None 3-20-97  
Operations Completed: Hour: 11:15 a.m. Day: 13 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1552' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE MAR 21 1997  
INV. NO. 477.87  
3-13

Signed Stephen J. Pfeifer (TECHNICIAN)