

1120853

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,535-0000  
200' N of  
SW SW SW, SEC. 16, T 25 S, R 16 W/XX  
530 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name:  
Address P.O. Box 8647  
Wichita, KS 67208

Lease Name Palmatier Well # 1  
County Edwards  
Well Total Depth 4426 143.84 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 20 Month: 10 Year: 19 93

Plugging proposal received from Joe  
(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4420' w/150 sx cement, PBTD 4422', Perfs at 4420-36, 4358-78'  
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by \_\_\_\_\_ Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12:45 p.m. Day: 27 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4300' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 200 lbs. hulls. Hole in 8 5/8"-unable to pump and plug.

10/27/93-Ran tubing to 1110' and pumped in 50 sx cement, tubing to 900' and pumped 10' sx gel,  
tubing to 425' and circulated cement with 140 sx cement. Pulled out tubing and topped with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1646' of 4 1/2" casing.  
If additional description is necessary, use BACK of this form.

INVOICED

(did / did not) observe this plugging.  
DATE: NOV 03 1993

INV. NO. 39140

Signed Duane Rankin  
(TECHNICIAN)

11-1-93  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 01 1993  
CONSERVATION DIVISION  
Wichita, Kansas