


15-185-11095-0000

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 18 1966
3-18-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Irma Smith Well No. # 2

Location NW SE SW Sec. 10 Twp. 25 Rge. 15 (E) (W)

County Stafford Total Depth 4070'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 2:00PM Day 12th Month March Year 1966

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cemented with 225 sacks. 4069' of 5 1/2" long
string, cemented with 300 sacks. Plug back TD 4012'. Top perferation 3926'.
Bottom of the hole was sanded to 3900', and cemented with 5 sacks. 2890'
of 5 1/2" long string was recovered from the hole. Fluid was up in the hole.
Bridge plug was pushed in fluid to 250', rock bridge from 250' to 240'.
8 sacks of cement was mixed in a barrel, and put on plug at 240', through
the dump bailer, and let set over-night. Next morning hole was bailed dry,
and 17 sacks of cement was added to the plug. Hole was filled with mud to 40'
rock bridge from 40' to 30', and cemented with 10 sacks to the base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/18/66

INV. NO. 2889-d