

15-055-00635-0000R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
OCT 21 1975
10-21-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Graham-Michaelis Corporation

Complete Address 211 N. Broadway, Wichita, Kansas

Lease Name Van Der Vee Well No. 1

Location C NW/4 Sec. 16 Twp. 26 Rge. (E) (W) 31

County Finney Total Depth 2677'

Abandoned Oil Well _____ Gas Well XX Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Sargents Csg Plg.

Address Liberal, Kansas License No. 511

Operation Completed: Hour 4 P Day 16 Month 10 Year 1975

The above well was plugged as follows:

Total depth 2677' 8 5/8 csg set 507' cwc

4 1/2 csg set 2677 CW 150 sk cem.

4 1/2 csg PFS (2626-2669)

Pumped 15sk plug W/200 lbs hulls -top of cem. 2500'.

Cutoff & recovered 732' of 4 1/2 csg.

Set 35 sk cem. plug at 500' thru 4 1/2 csg.

Set sold bridge at 35' & set 15 sk cmt plug (35' to base of cekar.)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 10/23/75

INV. NO. 2096-W