

KANSAS
STATE CORPORATION COMMISSION

15-655-00627-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1962 8-6-62

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 210 North Kansas, Liberal, Kansas

Lease Name Anna Hutton Unit Well No. 1

Location C SW/4 Sec. 3 Twp. 26 Rge. 31 (E) (W)

County Finney Total Depth 2681

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304 Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 2 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" C&P w/cement. 522'

4 1/2" 2681' cemented. Top of perf. 2642'

Plug bottom w/sand, cap w/2 sax. cement. 2682' to 2635'

Heavy mud 2635' to 245' Set plug 35 sax. cement.

Heavy mud to 40' Set 10' rock bridge, 10 sax. cement to top of surface.

(Shot 4 1/2" at 245')

(Co. Pump.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/6/62

INV. NO. 5492-w

Signed: [Signature]
Well Plugging Supervisor