

15-185-11909-0000
Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Western Petroleum Co., Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name Hart Well No. # 2

Location C N/2 SW Sec. 22 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4445

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Western Petroleum Co., Inc.

Address: 925 Patton Road, Great Bend, Kansas License No.

Operation Completed: Hour 1:30AM Day 27th Month Jan. Year 1964

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cemented with 320 sacks. Fluid was up in
hole. Plug was pushed to 275', with 1/2 sacks hulls, and cemented with 25
sacks through the drill pipe. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with hulls, and cemented with 10 sacks to
base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/29/64
INV. NO. 8545-W