

15-185-00293-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name: Isern - Wells Drilling Co.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Haynes Well No. # 1

Location NW NW SE Sec. 22 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4578

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers Inc.

Address: 1809 Lakin, Great Bend, Kansas License No. 462

Operation Completed: Hour 10:30AM Day 24th Month April Year 1963

The Above well was plugged as follows:

360' of 8 5/8" surface pipe cement circulated with 350 sacks. 4578' of  
5 1/2" long string cemented with 150 sacks. Plugged back to 4320'. Perferated  
from 4251' to 60'. Sanded to 4220', 10' rock bridge and 5 sacks cement.  
Plug was set at 225', 10' rock bridge, cemented with 3' sacks. Let set over  
night, bailed hole down, finished cementing with 17 sacks. Filled hole  
with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.  
3526' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/26/63  
INV. NO. 6965-w

Signed: Audie Elving  
Well Plugging Supervisor