

15-185-11102-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1967
2-16-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 18, 1967.

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Hart Well No. # 1

Location C SE NW Sec. 22 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4425'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Flugging Contractor: Bert Self Casing Pulling Company

Address: R. R. # 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 1:15PM Day 14th Month Feb. Year 1967

The Above well was plugged as follows:

984' of 8 5/8" surface pipe, cemented with 400 sacks. 4330' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 4300', and cemented with 5 sacks, through the dump bailer.
3910' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 315', bridge plug and rock bridge from 315' to 300'. 2 sacks of
Cal-Seal was mixed in a barrel, and put on plug at 305', through the dump
bailer, and let set over-night. Next day hole was bailed dry, and 25 sacks
of cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/16/67
INV. NO. 4772-u