

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-185-30185-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1965
10-22-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Wilson Well No. # 1

Location App. C SW SE Sec. 24 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 1859'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Raymond Oil Company, Inc.

Address: 410 Fourth National Bank Bldg., Wichita, Kans License No. _____

Operation Completed: Hour 8:00 PM Day 20th Month Oct. Year 1965

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level was up in the hole. 1st cementing plug and 1 sack of hulls was
pushed in fluid to 260', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/22/65

INV. NO. 2025-W