



15-185-21149-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Hunt of Montgomery Exploration has this date requested permission to plug the following described well:

Operator's Full Name: Montgomery Drilling Programs

Complete Address: P O Box 1114, Hays Kansas 67601

Lease Name: Wilson Well No. 12 2

Location: C SW SW Sec. 13 Twp. 25S Rge. 15 ~~(E)~~ (W)

County: Stafford Total Depth: 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hunt was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 540'.

Fill hole with mud and spot 30 sx cement at 270'.

Fill hole with mud to 40' and $\frac{1}{2}$ sx hulls, plug, and 10 sx cement.

10 sx cement in rat hole.

290' of 8 5/8" surface casing cement circ.

Very truly yours,

Dean Rankin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1980
CONSERVATION DIVISION
Wichita, Kansas

11-14-80