

15-185-01169-00017

FORM - CP-2
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

4-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill, filed
February 27, 1967.

Dear Sir:

Mr. Lonnie Lorrow of Kewanee Oil Company has this

date requested permission to plug the following described well:

Mr. LORROW guarantees payment of the plugging fee.

Operator's full Name: Kewnanee Oil Company

Complete Address: P. O. Box 2093, Wichita, Kansas

Lease Name: Barstow "A" Well No. # 1-X

Location: C NE NW NW Sec. 2 Twp. 25 Rge. 15 (E)(W) W

County Stafford Total Depth 3400' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. LORROW was instructed to plug the well as follows:

968' of 8 5/8" surface pipe. cement circulated/ Fill hole with mud
to 300', rock bridge from 300' to 290', and cement with 25 sacks.
Fill hole with mud to 40', rock bridge from 40' to 30', and cement
with 10 sacks to base of cellar.

Very truly yours,

Archie Elving
Conservation Division Agent