



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

12-2-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: VanWinkle "D" Well No. # 1

Location: NW SW SW Sec. 33 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4120 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

355' of 8 5/8" surface pipe, cemented with 350 sacks.
Fill hole with drilling mud to 300', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent