



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-055-00637-0006

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1965
5/24/65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lawrence of Kansas Neb. Nat. Gas Co. Inc. has this date requested permission to plug the following described well:

Mr. Lawrence guarantees payment of the plugging fee.

Operator's full Name: Kansas Neb. Nat. Gas Co. Inc.

Complete Address: Box 608 Hastings, Nebraska

Lease Name: Brensing Well No. # 2

Location: C NE Sec. 17 Twp. 26 Rge. 31 (W)

County Finney Total Depth 2704' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lawrence was instructed to plug the well as follows:

8 5/8" - 447' Circulated w/cement. 5 1/2" - 2694' Cemented. Top Perforations - 2640'

Plug bottom w/20 sax. cement top cement 2545' Mud 2545' to 450'

Spotted 35 sax. cement 450' to 350' Mud 350' to 45'

Plug, Hulls, 15 sax. cement 45' to 0

Very truly yours,

Conservation Division Agent