

15-185-30078-0000

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name Morrison Well No. # 1

Location NE NW SE Sec. 36 Twp. 25 Rge. 14 (E) (W)W

County Stafford Total Depth 3815'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 3:30 AM Day 28th Month June Year 1965

The Above well was plugged as follows:

345' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 120'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 300', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION
7-1-65

I hereby certify that the above well was plugged as herein stated.

INVOICED
CONSERVATION DIVISION
Wichita, Kansas
DATE 7/1/65
INV. NO. 1390-W

Signed: Archie Elving
Well Plugging Supervisor