

15-185-01461-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAY 14 1964
5-14-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Southards Well No. # 1

Location NW NW SW Sec. 33 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4493

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 6:00PM Day 13th Month May Year 1964

The Above well was plugged as follows:

599' of 8 5/8" surface pipe, cemented with 500 sacks. 4041' of 4 1/2"
long string, cemented with 100 sacks. Top perferation 3928'. Plug was
pushed to 3800', and 10' of rock bridge, cemented with 3 sacks. Fluid
level was up in the hole. Plug was pushed to 275', and 10' of rock
bridge, 3 sacks of cement and 15 lbs of Calcium Chloride, was mixed
in a barrel, and put on plug, through the dump bailer, and let set
for 4 hours. Hole bailed down, and 22 sacks of cement was added to

plug. Hole was filled with mud to 40', and 10' of rock bridge, cemented
with 10 sacks to base cellar. 3303' of 4 1/2" long string was recovered from hole
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/14/64
INV. NO. 9139-W