

15-185-0#169-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

4-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill, filed
February 27, 1967.

Operator's Full Name Kewanee Oil Company

Complete Address: P. O. Box 2093, Wichita, Kansas

Lease Name Barstow "A" Well No. # 1-X

Location C NE NW NW Sec. 2 Twp. 25 Rge. 15 (E) (W)W

County Stafford Total Depth 3400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This was a work over hole with the tools down to 3400'

Plugging Contractor: Jamison Drilling Company

Address: Box 56, Hoisington, Kansas License No.

Operation Completed: Hour 3:00PM Day 13th Month April Year 1967

The Above well was plugged as follows:

968' of 8 5/8" surface pipe, cement circulated. 4447' of 5 1/2" long string,
cemented to the top. No recovery of any pipe. Plug back T.D. 2925'. Top
perferation 2603'. Cast Iron bridge plug was set at 2575', above all per-
ferations, and 2 sacks of cement on plug, through the dump bailer at 2575'.
Hole was swabbed to 300', bridge plug and rock bridge from 300' to 290',
and cemented with 10 sacks of cement, from 290' to 210'. Hole was filled
with mud to 40', bridge plug and rock bridge from 40' to 30', and cemented
with 5 sacks, from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/67

INV. NO. 5061-W

Signed: Aubie Elving
Well Plugging Supervisor