

R

KANSAS

STATE CORPORATION COMMISSION

15-185-11093-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sierra Petroleum Co. Inc.

Complete Address 211 N Broadway Wichita, Ks

Lease Name Barstow Well No. 3

Location NE/SE/SE Sec. 2 Twp. 25 Rge. 15 (E) W

County Stafford Total Depth 4434

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 5:00 PM Day 2 Month 6 Year 1972

The above well was plugged as follows:

273 ft 8 5/8 surface pipe cemented with 200 sacks. 4433 ft 5 1/2 long
string cemented with 175 sacks. Top perf. 4190 ft. Sand back to
4175 ft, 5 sacks cement with bailer. Pulled 3600 ft 5 1/2. Pump 5 sacks
hulls, 20 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5821-11