

API NUMBER 15-185-229940000

LEASE NAME Wilson IT

WELL NUMBER No. 1

1980 Ft. from S Section Line
660 Ft. from E Section Line

SEC. 15 TWP. 25 RGE. 15 (N) or (W)

COUNTY Stafford

Date Well Completed 06-11-95

Plugging Commenced 8:30pm on 6-11-95

Plugging Completed 10:15pm on 6-11-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oil Producers Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, KS 67208

PHONE(S) (316) 681-0232 OPERATORS LICENSE NO. 8061

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 8th @ 8:30 am (date)

by Steve Middleton (KCC District Agent's Name).

Is ACG-1 filled? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	312'KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set

Plugged with 50 sx @ 990', 50 sx @ 330', 10 sx @ 40', and 15 sx in the ratihole.

Name of Plugging Contractor Sterling Drilling Company License No. 5142/ED COMMISSION

Address P.O. Box 1006, Pratt, KS 67124 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers Inc. of Kansas JUN 14 1995

STATE OF Kansas COUNTY OF Pratt, ss.

Steve E. McClain, President (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Steve E. McClain, President
P.O. Box 1006, Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1995

[Signature]
 Notary Public

My Commission Expires: July 3, 1996

USE ONLY ONE SIDE OF EACH FORM.



Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG**Wilson 'I' No. 1****LOCATION:** C Ne Se

Section 15 T 25S R 15W

Stafford County, Kansas

OWNER: Oil Producers, Inc. of Kansas**COMMENCED:** 06-Jun-95**CONTRACTOR:** Sterling Drilling Company, Rig #4**COMPLETED:** 12-Jun-95**TOTAL DEPTH:** DRILLER 4310 FEET**ELEVATIONS:** G.L. 2028

LOGGER 4295 FEET

K.B. 2037

LOG

0	-	35 FEET	Sand
35	-	200 FEET	Sand and Clay
200	-	315 FEET	Shales and Redbeds
315	-	505 FEET	Redbed and Shale
505	-	970 FEET	Shale
970	-	982 FEET	Anhydrite
982	-	4310 FEET	Lime and Shale

CASING RECORDS

SPUD @ 2:45 pm on 6-6-95. Drilled 12-1/4" hole to 315'. Ran 8 joints of used 28# 8-5/8" surface casing. 300.16' set at 312'KB.

Cemented with 200 sx 60/40 Poz, 2% Gel, 3% CC. Plug down @ 7:45pm by Howco with good returns, Ticket # 835114.

Started plugging well @ 8:30 pm 6-11-95 using 60/40 Poz 6% Gel. Plug down @ 10:15pm on 6-11-95 by HOWCO, Ticket # 835119.

Plugged well with 50 sx @ 990', 50 sx @ 330, 10 sx @ 40'. 15 sx in rathole.

DEVIATION SURVEYS

1/2 DEG. @ 315 FEET

1.25 DEG. 4310 FEET

RECEIVED
STATE COURT
6-14-95
JUN 14 1995
COMMISSION
CONSULTING ENGINEER