

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-185-11852-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 15 Twp. 25S Rge. 15W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NE/4 SW/4  
Lease Owner National Cooperative Refinery Association  
Lease Name HART "A" Well No. 2  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 20 19 60  
Application for plugging filed November 22 19 60  
Application for plugging approved December 1 19 60  
Plugging commenced November 20 19 60  
Plugging completed November 20 19 60  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4265 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"		None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 4265 feet to 240 feet. Set bridge, using 1/3 sack of hulls and 20 sacks of cement through drill pipe. Filled hole with heavy mud to 35 feet. Set bridge with 1/3 sack of hulls and 10 sacks of cement, filling on up to base of cellar.

12-5-60

STATE CORPORATION COMMISSION

DEC 5 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Company, Inc.  
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C.R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears (C.R. Sears)

305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of December, 19 60

My commission expires November 26, 1964

NELL McCOMB

Notary Public.



13-185-11852-0000

N. G. R. A. - Operator

SIERRA PETROLEUM CO., INC. - Contractor

HART #2  
C NE SW  
Sec. 15-25S-15W  
Stafford County, Kansas

T. D.: ~~1265~~ 4265'  
Elev.: 2033' K.B.

Commenced: 11-9-60  
Completed: 11-20-60

CASING:

8-5/8" Set @ 284'

CEMENT:

with 250 sx. cement

FORMATION

Sand & Gravel	195
Shale & Shells	284
Shale & Red Bed	963
Anhydrite	990
Shale & Shells	1400
Salt & Shale	1610
Shale & Shells	1875
Lime & Shale	3780
Lime	4057
Lime & Shale	4107
Lime	4235
Lime & Shale	4265

TOPS:

Anhydrite	963
Heebner	3618
Toronto	3637
Douglas	3658
Lans. K. C.	3790
Mississippi	4182

STATE OF KANSAS        )  
                                  ) ss:  
COUNTY OF RUSSELL    )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

C. R. Honaker

Subscribed and sworn to before me this 21st day of November  
1960.

Lesoy S. [Signature]  
(Notary Public)

My commission expires: 10-17-63

11-22-60  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1960  
CONSERVATION DIVISION