

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

No Fee
WJ
2/3

WELL PLUGGING RECORD

15-185-20367-0000

API NUMBER _____

LEASE NAME Cotton #1

WELL NUMBER _____

SPOT LOCATION C of SE SW

SEC. 8 TWP. 25S RGE. 15W (E) OR (W)

COUNTY Stafford

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9-22-83

PLUGGING COMPLETED 9-28-83

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P.O. Box 35528 - Tulsa, Okla. 74135

PHONE #() _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACC-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 4650'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	none
				5-1/2"	4600'	2182'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Squeezed 5-1/2" casing with 1 sack hulls and 100 sacks cement, pumped bottom plug to 3600'. Shot casing @3510', 3190', 3000', 2810', 2680', 2500', 2390', 2270', 2185' and pulled a total of 69 joints (2182') of 5-1/2" casing. Squeezed hole with 3 sks. hulls, 15 sks. gel, 40 sks. cement, 10 sks. gel, released plug and displaced with 1 sk. hulls and 85 sks. cement. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050

ADDRESS P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29th DAY OF September, 19 83

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83