

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-185-20367-0000

API NUMBER

LEASE NAME Cotton #1

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER

SPOT LOCATION C of SE SW

LEASE OPERATOR Leben Oil Corporation

SEC. 8 TWP. 25S RGE. 15W (E) OR (W)

ADDRESS P.O. Box 35528 Tulsa, Okla. 74135

COUNTY Stafford

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6566

DATE WELL COMPLETED

PLUGGING COMMENCED 9-22-83

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 9-28-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? IF NOT, IS WELL LOG ATTACHED?

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 4650'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	none
				5-1/2"	4600'	2182'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Squeezed 5-1/2" casing with 1 sack hulls and 100 sacks cement, pumped bottom plug to 3600'. Shot casing @3510', 3190', 3000', 2810', 2680', 2500', 2390', 2270', 2185' and pulled a total of 69 joints (2182') of 5-1/2" casing. Squeezed hole with 3 sks. hulls, 15 sks. gel, 40 sks. cement, 10 sks. gel, released plug and displaced with 1 sk. hulls and 85 sks. cement. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050

ADDRESS P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, SS.


R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29th DAY OF September, 19 83

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES:

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

OCT 5 1983

CONSERVATION DIVISION
Wichita, Kansas


COPY

WELL LOG

15-185-20367-0000

Company Leben Oil Corporation
Contractor Leben Drilling, Inc.
Farm Cotton #1
Total Depth 4650'
Commenced August 8, 1971
Completed August 21, 1971

Sec. 8 T.25S R. 15W
Loc. C SE SW
County Stafford County
Casing 8 5/8" w/ 150 sx.
Production 5 1/2" w/ 175 sx.



Figures Indicate Bottom of Formations

0'	-	215'	sd
215'	-	290'	sh
290'	-	500'	red bed & sh
500'	-	971'	red bed
971'	-	982'	anhy
982'	-	1505'	sh & shells
1505'	-	1986'	sh & lm
1986'	-	2190'	lm & sh
2190'	-	2400'	sh & lm
2400'	-	2730'	lm & sh
2730'	-	3015'	sh & lm
3015'	-	3595'	lm & sh
3595'	-	4212'	lm
4212'	-	4238'	lm & chert
4238'	-	4255'	lm
4255'	-	4305'	Miss. lm & chert
4305'	-	4357'	lm & chert
4357'	-	4402'	lm
4402'	-	4487'	lm - chert - sh
4484'	-	4534'	cherty lm & ch
4534'	-	4650'	cherty lm

8-8-83

RECEIVED
STATE CORPORATION COMMISSION
AUG 08 1983
CONSERVATION DIVISION
WELLS & MINES

State of Oklahoma
County of Oklahoma } SS

I, Leslie Kite of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Cotton #1 Well.

Leslie Kite

Subscribed and sworn to before me this 1st day of September 1971

My Commission Expires: 4-29-75 Jackie Brewer