


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-185-11909-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

STAFFORD County, Sec. 22 Twp. 25 Rge. 15 (W)

Location as "NE/CNW/SW" or footage from lines C. N/2 SW  
Lease Owner WESTERN PETROLEUM CO., INC.  
Lease Name HART Well No. 2  
Office Address P.O. BOX 524, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 1-26-64 19 64  
Application for plugging filed 1-26 19 64  
Application for plugging approved 1-26 19 64  
Plugging commenced 1-26 19 64  
Plugging completed 1-27 1:30 A.M. 1-27 19 64  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE V. ELWING  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4445 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	298	8-5/8	1-15-64	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PUSHED WOODEN PLUG AND HULLS TO 275' WITH DRILL PIPE. CEMENTED WITH 25 SXS CEMENT THROUGH DRILL PIPE.  
FILLED HOLE TO 40' WITH ROTARY MUD. PUSHED WOODEN PLUG AND HULLS TO FLUID. CEMENTED WITH 10 SXS CEMENT.  
JOB COMPLETED @ 1:30 A.M. 1-27-64.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 31 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
F. J. COPELAND (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. J. Copeland  
1201 WASHINGTON, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of JANUARY, 1964

My commission expires JANUARY 15, 1967  
REVA C. BROWN Notary Public.

15-185-11909-0000

DRILLER'S LOG  
HART #2

COMPANY: WESTERN PETROLEUM Co., Inc. ELEVATION: 2028 DF  
2030 KB  
CONTRACTOR: WESTERN PETROLEUM Co., Inc. CASING RECORD: 7 JTS. 8-5/8"  
28# USED CASING  
COMMENCED: JANUARY 15, 1964 TOTAL DEPTH: 4445'  
COMPLETED: JANUARY 27, 1964  
DESCRIPTION: C N/2 SW  
SECTION 22-T25S-R15W  
STAFFORD COUNTY, KANSAS

FORMATION	FROM	TO	REMARKS
SAND CLAY	-0-	40	RAN 7 JTS. 8-5/8" USED PIPE 28#, (290.99'). SET @ 298'. CEMENTED w/300 SXS COMMON CEMENT 2% GEL 3% C.C. PLUG DOWN @ 9:15 P.M. 1/15/64. CEMENT CIRCULATED.  DST #1- 4284-4307. OPEN 1 1/4 HRS, FAIR BLOW DECLINING TO WEAK. RECOVERED 215' WATERY MUD, 1BHP 1010#/45", FBHP 750#/45", FP 0-65#, INITIAL FLOW 15". HH 2200#. TD 4307.
SAND GRAVEL	40	220	
SHALE	220	289	
SHALE SHELLS	289	420	
RED BED	420	980	
ANYDRITE	980	1005	
SHALE	1005	1118	
SHALE SHELLS	1118	1825	
SALT & SHALE	1825	2035	
LIME & SHALE	2035	2401	
SHALE & LIME	2401	2540	
LIME & SHALE	2540	3685	
SHALE & LIME	3685	3811	
LIME	3811	3832	
LIME & SHALE	3832	3894	
LIME	3894	4069	
LIME & SHALE	4069	4128	
LIME	4128	4245	
LIME & CHERT	4245	4250	
LIME & SHALE	4250	4266	
LIME CHERT	4266	4307	
MISS. CHAT	4307	4350	
CHERT	4350	4445	
TD	4445		
<u>ELECTRIC LOG TOPS</u>			
HEEBNER	3648	-1618	
BR. LIME	3812	-1782	
LANSING	3820	-1790	
B/KC	4098	-2068	
CONGLOMERATE	4232	-2202	
MISSISSIPPIAN	4284	-2254	
KINDERHOOK	4336	-2306	
VIOLA	4400	-2370	

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF BARTON ) SS

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

*F. L. Coreland*  
F. L. CORELAND, DRILLING SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 30TH DAY OF JANUARY, 1964.

*Reva C. Brown*  
REVA C. BROWN, NOTARY PUBLIC

MY COMMISSION EXPIRES JAN. 15, 1967