


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-185-01157-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 22 Twp. 25S Rge. 15W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW SW  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name HART Well No. 1  
Office Address 208 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-30-60 19  
Application for plugging filed 5-29-60 19  
Application for plugging approved 5-29-60 19  
Plugging commenced 5-29-60 19  
Plugging completed 5-30-60 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot, St. John, Kansas.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale	8-5/8" Casing	-0-	230'	8-5/8"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED: Filled hole with heavy mud 4545' up to 220'.  
Set bridge using 1/3 sk. hulls, wood plug,  
20 sx. cement through drill pipe. Filled  
with heavy mud up to 35'. Set bridge using  
1/2 sk. hulls, wood plug, 10 sx. cement to  
cellar zero.

Job Completed: 3 a.m. 5-30-60.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.  
C. T. HONAKER (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRUG. SUPT.

Box 232, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of MAY, 19 60

Jeray Diehl  
Notary Public.

My commission expires 10-17-63

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1960 6-1-60

CONSERVATION DIVISION

15-185-01157-0000

SIERRA PETROLEUM CO., INC. ET AL: Operators  
SIERRA PETROLEUM CO., INC. : Contractor

Elevation: 2027 K.B.  
T. D. : 4545

HART #1  
NW NW SW  
Sec. 22-25S-15W  
Stafford County, Kansas

Commenced: 5-14-60  
Completed: 5-30-60

CASING:

8-5/8" Set @ 230

CEMENT:

with 175 sacks

FORMATION	DEPTH
Sand & Shale	130'
Sand	195'
Shale	290'
Red Bed	957'
Anhydrite	981'
Shale & Shells	1370'
Salt & Shale	1550'
Shale & Shells	1880'
Lime & Shale	3807'
Lime	4220'
Mississippi	4247'
Kinderhook	4304'
Viola	4450'
Viola	4461'
Simpson	4522'
Arbuckle	4545'
TOPS:	
Anhydrite	957'
Heebner	3632'
Tornoto	3653'
Douglas	3673'
Brown Lime	3785'
Lans. K. C.	3797'
Mississippi	4217'
Kinderhook	4230'
Viola	4304'
Simpson	4461'
Arbuckle	4518'

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

A. P. Housler

Subscribed and sworn to before me this 31st day of May  
1960.

Geroy Diez  
Notary Public

My commission expires: 10-17-63