

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-069-20,223-00-00

LEASE NAME Monger

WELL NUMBER 7

1650 Ftt. from S Section Line

1650 Ftt. from E Section Line

SEC. 20 TWP. 26 RGE. 29 (E) or (W)

COUNTY Gray

Date Well (Completed) _____

Plugging Commenced 7/30/03

Plugging Completed 8/1/03

AUG 15 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St., Suite 500, Denver, Colorado

PHONE# (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 30, 2003 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 4982' Bottom 4996' T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	282	8 5/8"		no
	Production	0	5049	4 1/2"		no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Tubing & rods are parted at 1300' from surface. LK Wireline set a CIBP at 1050', pressured casing and plug to 300#'s and it held. Perforated 3 holes at 960'. Swift Cementers pumped 135 sks of 60/40-6% gel down the 4 1/2" casing at 1200#'s pressure, ISIP 850#'s. Pressured the 8 5/8" casing to 800#'s and could not put any cement down it. Shut casing in, cement in the 4 1/2" from surface to 960'

Name of Plugging Contractor Encore Operating Company License No. 33069

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company

STATE OF Colorado COUNTY OF Denver, s.s.


Roland Nyp

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS



SUBSCRIBED AND SWORN TO before me this 13th day of August, 2003

Jane R. Nyp
Notary Public

My Commission Expires: 9-30-04