

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-069-20123-0000

LEASE NAME Monger

WELL NUMBER 2

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 20 TWP. 26 RGE. 29 (E) or (W)

COUNTY Gray

Date Well Completed 6/12/81

Plugging Commenced 11/8/93

Plugging Completed 11/9/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Asher Association Inc.

ADDRESS 2350 E. Williamette Lane, #310

Greenwood Village, CO 80121

PHONE# (303) 721-6367 OPERATORS LICENSE NO. _____

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, Is well log attached? _____

Producing Formation _____ Depth to Top 4960 Bottom 4971 T.D. 5085

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Oil & Water	4960	4971	8 5/8"	450'	0
				4 1/2"	5069'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 4 1/2" @ 5069' w/125 sx cmt. Perfs @ 4960-71'. Pkr. stuck @ 4590'. 1st plug set CIBP @ 4500'. Perforated @ 1000'. 2nd plug pump 160 sx cmt dwn csg. 3rd plug pump 160 sx cmt dwn backside. 8/9 Set CIBP @ 4500', loaded csg to test well took 50 bbl, well on vac. 8/10 Ran free point, pipe stuck @ 520' f/surface. Ran tbg & pkr. to isolate leak. Found @ 1280' f/surface. 8/11 - On back (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF _____ COUNTY OF _____, ss.


4-11-94

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan Hays

(Address) P.O. Box 130, Hill City, KS

RECEIVED
STATE CORPORATION COMMISSION



AND SWORN TO before me this 8th day of April

Donna Gerstner

Notary Public
CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: 6/24/97

Set CIBP @ 1100'. Perforated casing at 975'. Pumped in 160 sacks cement down 4 1/2". Shut in pressure 200 psi. Hooked onto backside and pumped in 165 sacks cement. Shut in 0 psi and maximum pressure 400 psi. Used 60/40 Pozmix 6% gel by Allied. No casing recovery.