

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20535-0000

LEASE NAME Palmatier

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

530 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Oil Producers of Kansas

SEC. 16 TWP. 25S RGE. 16 (E) or (W)

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

COUNTY Edwards

PHONE# (316) 672-6373 OPERATORS LICENSE NO. 8061

Date Well Completed 11-06-79

Character of Well oil

Plugging Commenced 10-11-93

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 10-11-93

The plugging proposal was approved on 10-10-93 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? No

Producing Formation Kinderhook Depth to Top 4420' Bottom 4436' T.D. 4436
Mississippi 4358' 4378'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Top		8 5/8"	365'	0
				4 1/2"	4420'	1646.20

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Top plug: sand to 4280' bailed 4 sacks of cement, started pumping hole in 8 5/8"
Bottom plug: Ran 1100' of tubing, pumped 3 sacks gel, 50 sacks of cement, pulled 7 joints, pumped 10 sacks of gel, pulled 11 joints, pumped 140 sacks of cement, circulated, pulled tubing off with 10 sacks of cement.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 28 day of October, 19 93

Karlynn K. Beck
Notary Public

RECEIVED

STATE CORPORATION COMMISSION

10-29-93

OCT 29 1993

My Commission Expires: 09-21-94
USE ONLY ONE SIDE OF EACH FORM

KARLYNN K. BECK
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 9-21-94

Form CP-4
Revised 05-88
CONSERVATION DIVISION
Wichita, Kansas