

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Edwards County. Sec. 5 Twp. 25 Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines. SW SW SW
Lease Owner Joe Branum
Lease Name Breitenbach Well No. 1
Office Address Box 286, Larned, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) washdown
Date well completed 19
Application for plugging filed January 16 1968
Application for plugging approved 19
Plugging commenced January 17 1968
Plugging completed January 22 1968
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes Archie Elving

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4574 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	none
				5-1/2"	4498'	2451.55'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4470' - 4350'	sand
4350' - 4310'	5 sacks cement
4310' - 225'	mud
225' - 215'	rock bridge - 1 sack calseal
215' - 140'	25 sacks cement
140' - 40'	mud
40' - 30'	rock bridge
30' - base	10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of February, 19 68

My commission expires July 31, 1970

[Signature]
Notary Public.