


15-185-21073-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 19 Twp. 25S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
165' North of C S/2 SE/4
Lease Owner Beren Corporation
Lease Name Bryce #1 Well No. 1
Office Address 970 Fourth Financial Center, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed August 8, 1980 19
Application for plugging filed August 8, 1980 19
Application for plugging approved August 8, 1980 19
Plugging commenced 2:00 AM, August 9, 1980 19
Plugging completed 3:30 AM, August 9, 1980 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4375'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	413'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
50 sacks at 390', 1/4 sack
hulle and solid bridge at 40';
10 sacks Common cement with 4% gel
at 10'. 5 sacks in rat hole and
5 sacks in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Bernard Laudermilk (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard Laudermilk
STERLING DRILLING COMPANY
Bernard Laudermilk, President
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 80.

My commission expires



Charles M. Hall, Notary Public.

15-185-21073-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - BRYCE #1
Located: 165' North of C S/2 SE/4, Section 19-25S-15W,
Stafford County, Kansas

OWNER: Beren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 31, 1980
COMPLETED: August 9, 1980

TOTAL DEPTH: 4375'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 415 Sand and Shale	Ran 10 joints 8 5/8" casing, 398.67' set at 413' K.B. Cemented with 300 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 3:45 PM, 7-31-80, by Allied.
415 - 1410 Shale	
1410 - 4283 Lime and Shale	
4283 - 4305 Lime	
4305 - 4375 Lime and Shale	Plugged.

Deviation Surveys: 1 1/2° at 2028'
1 1/4° at 4375'

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1980
CONSERVATION DIVISION
Wichita, Kansas