


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 27 Twp. 25 Rge. 15 XXW
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
150' NW of C NW NE
Lease Owner White & Ellis Drilling, Inc.
Lease Name Hostetler Well No. 1
Office Address 7701 E. Kellogg Suite 290 Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed 11/16/79 19
Application for plugging filed 11/16/79 19
Application for plugging approved 11/16/79 19
Plugging commenced 11/16/79 19
Plugging completed 11/16/79 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	288'	

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet feet for each plug set.

11/16/79 Mud to 290', plug, plugged with 40 sacks cement.
11/16/79 Mud to 40', plug, plugged with 10 sacks cement.
11/16/79 Plugged with 5 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
Box 448, El Dorado, Ks. 67042

STATE OF Kansas COUNTY OF Butler, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
El Dorado
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of November, 1979

L. B. AUER
Butler County, Ks.
My Appt. Exp. Sept. 26, 1980

(Signature) L. B. Auer
Notary Public.

My commission expires

DRILLERS LOG

15-185-20980-0000

OPERATOR: White & Ellis Drlg. Inc.; 7701 E. Kellogg; Suite 290; Wichita, Ks.
 CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Hostetler Well No. 1
 Sec. 27 T. 25 R. 15W Spot 150' NW OF C NW NE
 County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 288' with 250 Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 4325' KB

Drilling Commenced: 11/5/79 Drilling Completed 11/16/79

Formation	From	To	Tops
Cellar	0	7	Anhydrite - 2050
Shale, Sand	7	2045	
Shale, Lime	2045	3550	
Lime	3550	3925	
Shale, Lime	3925	4095	
Lime	4095	4254	
Sand, Shale	4254	4266	
Sand, Lime	4266	4325	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Initial Production: _____

Electric Log _____

RECEIVED
 STATE CORPORATION COMMISSION

DEC 17 1979 12-17-79
 Type and Depths Covered
 CONSERVATION DIVISION
 Wichita, Kansas