


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-185-00288-0000  
WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Stafford County. Sec. 27 Twp. 25S Rge. 15 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SW/4 NW/4  
Lease Owner National Cooperative Refinery Association  
Lease Name Thomas Hart Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 18, 19 59  
Application for plugging filed July 21, 19 59  
Application for plugging approved July 23, 19 59  
Plugging commenced July 18, 19 59  
Plugging completed July 18, 19 59  
Reason for abandonment of well or producing formation Incapable of commercial  
production.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 4363 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	336'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Filled hole with mud to 280'. Set Plug with 1/2 sack of hulls plus 20 sacks of  
cement. Mudded hole to 40'. Set plug with 10 sacks of cement. Filled on up to  
base of cellar.

STATE CORPORATION COMMISSION

JUL 30 1959

7-30-59

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ari-Kan Drilling Company  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears. (C. R. Sears)

305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of July, 1959

My commission expires November 26, 1960

Nell McComb

Notary Public.

PLUGGING  
FILE SEC. 27 T. 25 R. 15 W  
BOOK PAGE 52 LINE 34

Company - National Cooperative Refinery Association

Description: C SW NW of  
Section 27-25S-15W  
Stafford County

Farm: Hart No. 1

Total Depth: 4,363'

Elevation: 2017 DF  
2019 KB

Comm: 7-1-59 Comp: 7-18-59

Contractor: Ari-Kan Drilling Company

Casing: Set 3361' 8 5/8" 24# new J and L casing - 11 jts  
with 250 sks cm cement - 2% c.c. Cement circulated.

Figures below indicate bottom of formation:

Surface clay and sand	130'
Sand	250
Sand shale	280
Red Bed	970
Anhydrite	985
Shale and shells	1865
Lime and Shale	2005
Lime	2180
Lime and shale	2275
Lime	2435
Lime and shale	3430
Lime	3598
Shale and Lime	3807
Lime	4215
Lime, shale and sand	4245
DST #1	4245
Lime	4310
Chert and shale	4327
Lime	4345
Chert and Lime	4363
T. D.	4363'

TOPS:

Anhydrite	970	/ 1049
Heebner	3652	- 1633
Toronto	3676	- 1657
Douglas	3702	- 1683
Brown Lime	3808	- 1789
Lansing	3819	- 1800
Cherokee Sand	4232	- 2213
Mississippi	4269	- 2250
Kinderhook Chert	4310	- 2291
Kinderhook Shale	4322	- 2303
RTD	4363	- 2344

RECEIVED  
STATE BARFORD INT. COMMISSION  
AUG 3 1959  
CONSERVATION DIVISION  
Wichita, Kansas

8-3-59

This is to certify that the above information is to the best of my knowledge true and correct.

ARI-KAN DRILLING COMPANY

By RL Kugel

Subscribed and sworn to before me this 29th day of July, 1959.

My commission expires April 1, 1963

Ulada Nichols  
Ulada Nichols - Notary Public

PLUGGING

FILE SEC. 27 T. 25 R. 15W  
BOOK PAGE 52 LINE 34