


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County, Sec. 30 Twp. 25S Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines. G SW/4 NW/4
Lease Owner Chief Drilling Co., Inc.
Lease Name Lamb Well No. 1-B
Office Address P. O. Box 797, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 5-20-61 19
Application for plugging filed 5-20-61 19
Application for plugging approved 5-20-61 19
Plugging commenced 5-20-61 19
Plugging completed 5-20-61 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4425 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 394' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set wooden plug and 1/3 sack hulls at 350'.
Mixed 20 sacks cement through drill pipe.
1/3 Sack of hulls, wooden plug set at 35'.
Mixed 10 sacks cement through drill pipe. 5-24-61

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address P. O. Box 797, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. Richard Hoover*
V. Richard Hoover, President
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 61

My commission expires October 3, 1964

Helen E. Fischer
Helen E. Fischer Notary Public.



WELL LOG

Chief Drilling Co., Inc.
P. O. Box 797
Great Bend, Kansas

No. 1-B Lamb
C SW/4 NW/4 Sec. 30-25S-15W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 5-8-61
Completed: 5-20-61

Casing Record: 8-5/8" @ 394' cemented with 340 sacks Sunset Cement.

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>ELEVATION</u> |
|----------------------------|-------------|-----------|------------------|
| Sand and Shale | 0 | 392' | 2043' Gr. |
| Red Shale | 392' | 700' | 2045' D.F. |
| Red Shale, Sand and Shells | 700' | 1010' | 2048' K.B. |
| Anhydrite | 1010' | 1025' | |
| Shale and Shells | 1025' | 1945' | |
| Shale and Lime | 1945' | 1965' | |
| Lime with Shale Streaks | 1965' | 2085' | |
| Lime | 2085' | 2290' | |
| Lime with Shale Streaks | 2290' | 2420' | |
| Lime | 2420' | 2505' | |
| Shale and Lime | 2505' | 2705' | |
| Lime and Shale | 2705' | 3230' | |
| Shale and Lime | 3230' | 3395' | |
| Lime and Shale | 3395' | 3735' | |
| Lime | 3735' | 4315' | |
| Sand and Lime | 4315' | 4330' | |
| Cherty Sand | 4330' | 4345' | |
| Sand | 4345' | 4360' | |
| Chert and Shale | 4360' | 4413' | |
| Chert | 4413' | 4425' | |
| Total Depth | 4425' | | |

FORMATION TOPS

| | | |
|--------------------|-------|---------|
| Anhydrite | 1010' | (+1038) |
| Heebner | 3706' | (-1658) |
| Brown Lime | 3852' | (-1804) |
| Lansing | 3862' | (-1814) |
| Cherokee Shale | 4288' | (-2240) |
| Cherokee Sand | 4297' | (-2249) |
| Conglomerate Chert | 4318' | (-2270) |
| Viola | 4413' | (-2365) |
| Total Depth | 4425' | (-2377) |

RECEIVED
STATE CORPORATION COMMISSION
5-24-61
MAY 24 1961

STATE OF KANSAS, COUNTY OF BARTON) SS.

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW/4 NW/4 Sec. 30-25S-15W, Stafford County, Kansas to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 20th day of May, 1961.

Helen E. Fischer
Helen E. Fischer, Notary Public

My commission expires: October 3, 1964.