

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

15-185-20654-0000

FORM CP-4

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Stafford County, Sec. 33 Twp. 25 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines G NW NW
Lease Owner Alpine Drilling Co., Inc.
Lease Name Frack Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil 67202
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 30 1976
Plugging completed July 6 1976
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4374

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			292'	8 5/8"	292'	none
			4373'	4 1/2"	4373'	3987.45
7-12-76	JUL 12 1976					
	CONSERVATION DIVISION WICHITA, KANSAS					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 4280'; sanded back to 4250' and dumped 4 sacks of cement.

Allied Cementing Company plugged well pumping in 2 sacks of hulls, 10 sacks of gel and 100 sacks of cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON
Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1976

My commission expires

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Notary Public.

15-185-20654-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FRACK #1

Located: C NE NE, Section 32-25S-15W, Stafford County,
JWNW Kansas 33

OWNER: Alpine Drilling Company, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 6, 1976
COMPLETED: May 15, 1976

TOTAL DEPTH: 4374'

LOG

0 - 180	Sand and Clay
180 - 292	Shale and Red Bed
292 - 993	Shale, Red Bed and Sand
993 - 1008	Anhydrite
1008 - 1130	Shale
1130 - 1830	Shale and Shells
1830 - 2030	Shale and Lime Strs.
2030 - 3900	Lime and Shale
3900 - 4120	Lime
4120 - 4210	Lime and Shale
4210 - 4270	Cherty Lime and Shale
4270 - 4302	Lime and Sand
4302 - 4344	Chert and Lime
4344 - 4353	Shale
4353 - 4374	Sand and Shale

CASING RECORD

Ran 7 joints 8 5/8", 28#, 8V, Rge 3
used casing, 280' set at 291' K.B.
with 225 sacks Common with 2% gel
and 3% cc. Plug down at 2:15 PM,
5-6-76.

RECEIVED
LAND CONSERVATION COMMISSION

JUN 29 1976 6-29-76

CONSERVATION DIVISION
Wichita, Kansas

YOUR COPY

Ran 110 joints 4 1/2", 10.5# new
seamless casing, set at 4373' K.B.
Cemented with 100 sacks Common cement.
Plug down at 11:45 AM by Allied,
5-15-76.