


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-185-00276-0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 35 Twp. 25S Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. NE/4 NE/4 SW/4
Lease Owner Birmingham-Bartlett Drilling Co. et al
Lease Name Frack Well No. 1
Office Address 300 Kaufman Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 6 19 53
Application for plugging filed (Verbal) April 6 19 53
Application for plugging approved (Verbal) April 6 19 53
Plugging commenced April 6 19 53
Plugging completed April 6 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? C. D. Stough granted permission

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle test Depth to top Bottom Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	306'	8-5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged hole with 20 sacks cement mixed and poured
through drill pipe on bottom plug set at 300'
10 sacks cement on top plug

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1953
CONSERVATION DIVISION
WICHITA, KANSAS
4-10-53

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address 300 Kaufman Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., owner and operator,
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery
300 Kaufman Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 53.

My commission expires November 29, 1954

Vivian J. Ginger
Notary Public.

24-2675-5 2-52-20M

PLUGGING
FILE SEC 35 T 25 R 5W
BOOK PAGE 9/ LINE 3

FRACK NO. 1 WELL

LOCATION: NE/4 NE/4 SW/4
Section 35-25S-15W
Stafford County, Kansas

SPUDED: 3-21-53
COMPLETED: 4-6-53

OPERATOR and
CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" casing cemented at 306'
with 225 sacks cement and 2 cc.

OIL STRING: None set. Dry and abandoned.

LOG

(Figures indicate bottom of formation)

0 -	260	Sand
	306	Shale and red bed
	955	Red bed
	980	Anhydrite
	1875	Shale and shells
	2390	Broken lime
	3250	Shale and shells
	3470	Shale and lime
	3605	Lime
	3675	Lime and sand
	3725	Lime
	3849	Shale and lime
	4160	Lime
	4205	Lime and shale
	4345	Lime
	4367	Chert and shale
	4405	Shale and lime
	4470	Lime
	4495	Cherty lime
	4670	Lime
	4595	Shale
	4620	Lime
	4620	RTD

4-10-53

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Frack No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
this 7th day of April 1953.

Vivian J. Yinger
Notary Public

My commission expires November 29, 1954

PLUGGING
FILE SEC 35T-25R-15W
BOOK PAGE 21 LINE 3