

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

057

API NUMBER 15-157-20,105-

LEASE NAME Maxwell 0000

WELL NUMBER "B" #1

SPOT LOCATION W/2-W/2-SE/4

SEC. 22 TWP. 26 RGE. 24 (E) or (W)

COUNTY Ford

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-28-84

Plugging Completed 8-3-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS Box 1303, Great Bend, Ks. 67530

PHONE # (316)-793-5472 OPERATORS LICENSE NO. 5123

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	574'	None
				4-1/2"	5102'	2,788.44'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 4950' and 4 sacks cement. Shot casing at 4400', 4000', 3500', 3000' and 2800'. Pulled 63 joints of 4-1/2" casing. Squeezed well with 3 sacks hulls, 14 sacks gel and 200 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Ks. 67530 8-7-84

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1984

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires: \_\_\_\_\_

Iona M. Leatherman  
Notary Public


**KANSAS DRILLERS LOG**

S. 22 T. 26S R. 24W E. W

Loc. W/2 W/2

County Ford

640 Acres  
N



Locate well correctly  
2551

Elev.: Gr.

DF 2553 KB 2556

API No. 15 — 957 — 20105-0000  
County Number

Operator  
**PICKRELL DRILLING COMPANY**

Address  
**205 LITWIN BLDG., WICHITA, KS. 67202**

Well No. 1 Lease Name **MAXWELL "B"**

Footage Location  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor **PICKRELL DRILLING COMPANY** Geologist **Brad Rine**

Spud Date 10-11-77 Total Depth 5110 P.B.T.D.

Date Completed 11-15-77 Oil Purchaser **NCRA**

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
SURF. CASING		8 5/8		574		300	
PROD. CASING		4 1/2		5100		150	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			4	DP	4999-5009
<b>TUBING RECORD</b>			4	DP	4995-4999
Size	Setting depth	Packer set at			
2 3/8	4993				

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval
	RECEIVED STATE CORPORATION COMMISSION JUL 17 1984 CONSERVATION DIVISION Wichita, Kansas

**INITIAL PRODUCTION**

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
1-6-78	Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	48 bbls.	100 MCF	48 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s) 4995-5009	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

COMPANY: PICKRELL DRILLING COMPANY  
 205 LITWIN BLDG.  
 WICHITA, KS. 67202

LOCATION: Maxwell "B" #1  
 W/2 W/2 Sec. 22-26S-24W  
 Ford County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
 Wichita, Kansas

Rotary Drilling Commenced 10-11-77  
 Rotary Drilling Completed 10-21-77

CASING RECORD:

Surf. casing 8 5/8" set at 574' with 300sx.  
 Prod. casing 4 1/2" set at 5100' with 150sx.  
 5102

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Clay-Sand	380
Sand	425
Shale	530
Shale	555
Red-Beds	580
Shale & Red Beds	1066
Shale	1159
Sand	1258
Shale	1485
Shale	1632
Shale & Lime Streaks	2026
Shale & Lime	2465
Shale & Lime	2665
Lime & Shale	2837
Lime & Shale	2955
Lime & Shale	3070
Lime & Shale	3253
Lime & Shale	3388
Lime & Shale	3505
Lime & Shale	3662
Lime & Shale	3784
Lime & Shale	3940
Lime & Shale	4153
Lime & Shale	4270
Lime	4375
Lime & Shale	4515
Lime	4615
Lime & Shale	4717
Lime & Shale	4797
Lime	4850
Lime	4933
Lime & Shale	5020
Lime	5110

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 17 1984  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]  
 Attorney-in-Fact  
 C. W. Sebitts

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 14 day of February, 19 78, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: \_\_\_\_\_

[Signature]  
 Notary Public

Jo Ann Sarver



BAKER OIL TOOL S, INC. 15-057-20105-0000

SERVING THE WORLD

DATE 1-5-81 WELL NO. 1 LEASE Maxwell B FIELD Conrady

ELEV.

2556 KB

2551 GL

574' Base 8 5/8 w/300 Sx

ESTIMATED Top of Cement 4480'

4995-4999 (Morrow Perfs)

5047 PBT D

5102 Base 4 1/2" 10.5# K-55 w/150 Sx

5110 T.D.

RECEIVED: STATE CORPORATION COMMISSION

JUL 17 1984

CONSERVATION DIVISION Wichita, Kansas



BRIDGE PLUG



PACKER



CENTRALIZER



SCRATCHER



BASKET



PERFORATION