

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Greenwood "B"
 Location 330' North and 330' East of Center Sec. 2 T. 25 R. 15W
 Elevation 2017 County Stafford State Kansas
 Drlg. Comm. August 4, 1943 Contractor Corbett-Barbour Drilling Company
 Drlg. Comp. August 31, 1943 Acid None
 T. D. 4485' Initial Prod. Dry - Plugged and Abandoned

CASING RECORD:

10-3/4" ϕ 238' cen. 150 sx cement

FORMATION RECORD:

sand	0-160
sand & shale	238
red bed, shale & shells	495
red bed	895
red bed, shale & shells	1150
shale & lime	1465
shale	1480
salt	1600
shale & lime	1780
shale & shells	1995
shale	2010
lime	2205
sandy lime	2275
sand	2310
lime & shale	2385
lime	2500
shale & shells	2585
shale & lime	2800
lime	2848
lime & shale	2905
shale & lime	3055
lime & shale	3120
shale & lime	3230
lime & shale	3300
shale & lime	3400
lime & chert	3415
lime & shale	3421
broken lime	3515
shale & lime	3565
lime	3594
shale & lime	3640
lime & shale	3695
shale & lime	3745
lime & shale	3780
lime	3963
lime & shale	4010
lime	4058
lime & shale	4090
shale & lime	4272

chert	4176
lime	4190
shale & lime	4235
lime	4243
cherty lime	4263
chert	4275
lime	4299
cherty lime	4307
lime	4322
chert	4326
lime	4335
shale & sand	4360
lime	4385
lime & shale	4420
shale	4433
cored sand (rec. 9 1/2')	4443
lime	4485 T. D.

Top Arbuckle 4443'
 Penetration 42'
 Total Depth 4485'

Halliburton drill stem test 3904-3914, recovered 15' rotary mud in 30 minutes.

Drill stem test, 3934-3955, rec. 165' salt water in 30 minutes.

Drill stem test, 4424-4433, rec. 30' mud and 30 minutes.

Syfo: 1000' 0°
 1500' 1°
 2000' 1°
 2500' 0°
 3500' 0°

PLUGGING

FILE SEC. 2-25R-15W
 BOOK PAGE 90 LINE 2

10-16-43