

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4429' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4424 1/2'	2189.69'
				8 5/8"	278'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3875'. Mixed and ran 5 sacks cement thru dump
bailer.
Squeezed hole with 3 sacks hulls - 20 sacks gel and 2 sacks hulls. Released plug and
displaced with 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5 day of June, 19 72

My commission expires October 1972



Sidney D. Miller
Notary Public.

15-185-00255-0000

Sierra Petro. Co. & Houston - Owners

Sierra Petroleum Co. - Contr.

BARSTOW #1

SW SE SE Sec. 2-25-15W
Stafford County, Kansas

Total Depth: 4429'

Elev: 2018 K.B.

Comm: 8-15-59

Comp: 8-31-59

Casing:

8-5/8" @ 278'

5-1/2" @ 4424 1/2'

Cement:

w/200 sx Pozmix HAS cement

w/175 sx Common Cement

FORMATION

DEPTH

Sand - Gravel
Shale - Shells
Shale
Red Bed
Anhydrite
Shale - Shells
Salt - Shale
Shale - Lime
Lime
Lime - Shale
Chert - Lime - Shale
Miss. Chert
Miss.
Kinderhook
Cherty Lime
Shale - Lime

150'
277'
310'
965'
990'
1425'
1600'
3745'
4038'
4113'
4208'
4220'
4243'
4287'
4349'
4429'

TOPS

Anhydrite
Helmser
Toronto
Douglas
Brown Lime
Lens. K. C.
Base K. C.
Conglomerate
Mississippi
Kinderhook
Viola
Arbuckle

965'
3604'
3624'
3636'
3745'
3767'
4038'
4118'
4198'
4234'
4281'
4424'

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1972
CONSERVATION DIVISION
Wichita, Kansas

5-17-72

STATE OF KANSAS

COUNTY OF RUSSELL

ss:

I hereby certify that the above information is true and
correct to the best of my knowledge.

C. P. Henaker

Subscribed and sworn to before me this 1st day of September, 1959.

Leroy Lutz
Notary Public

My commission expires: 10-17-59.