

15-185-11093-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Stafford County, Sec. 2 Twp. 25 Rge. 15 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner Sierra Petroleum Co.

Lease Name Barstow Well No. #3

Office Address Box 232 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5-30-72 19

Plugging completed 6-2-72 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4434' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4433'	3633.24'
				8 5/8"	273'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4175'. Mixed and ran 5 sacks cement thru dump bailer.

Squeezed hole with 3 sacks hulls - 20 sacks gel and 2 sacks hulls. Released plug and displaced with 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. C. Spencer Sec.

Box 364 Great Bend, Kansas

(Address)

Subscribed and Sworn to before me this 5 day of June, 1972

My commission expires



Sidney D. Miller
Notary Public.

15-185-11093-0000

SIERRA PETROLEUM CO., INC - ET AL / Operators

T. D.: 4434'
Elev.: 2027' K.B.

BARSTOW #3
NE SE SE
Sec. 2-25S-15W
Stafford County, Kansas

Commenced: 11-21-60
Completed: 12-2-60

Casing:

8-5/8" Set @ 273'
5-1/2" Set A 4433'

Cement:

with 200 sz. cement
with 175 sz. cement

FORMATION

DEPTH

Sand
Sand & Gravel
Shale & Shells
Shale
Red Bed & Shale
Red Bed
Anhydrite
Shale & Shells
Shale & Salt
Shale & Shells
Shale & Lime
Lime
Lime & Shale
Mississippi
Shale
Shale & Lime
Viola
Shale & Lime
Arbuckle

40
170
273
300
845
977
1005
1330
1560
1850
3760
4061
4223
4241
4256
4293
4382
4430
4434

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1972
CONSERVATION DIVISION
Wichita, Kansas
5-17-72

STATE OF KANSAS)
COUNTY OF RUSSELL)

ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker

Subscribed and sworn to before me this 5th day of December 1960.

James D. [Signature]
Notary Public

My commission expires: 10-17-63