


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-185-01007-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 2 Twp. 25S Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner SIERRA PETROLEUM CO., INC.
Lease Name BARSTOW Well No. 2
Office Address 208 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 4, 19 59
Application for plugging filed December 4, 19 59
Application for plugging approved December 4, 19 59
Plugging commenced December 3, 19 59
Plugging completed 1 a.m. December 4, 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	283'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud 4430' up to 240'. Set bridge, with 1/3 sk. hulls, wood plug, 20 sks. cement through drill pipe. Filled hole with mud up to 35'. Set bridge using 1/2 sk. hulls, wood plug, 10 sks. cement to cellar zero.

Job completed - 1 a.m. 12-4-59. Frank Broadfoot, St. John, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Russell, ss.
C. T. HONAKER, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 59

My commission expires 10-17-63

Geroy Dietz
Notary Public.



15-185-01007-0000

Sierra Petroleum Co., Inc. - Operator

BARSTOW #2
SE SW SE
2-25S-15W
Stafford Co., Kansas

Elevation: 2021 K.B.
T. D. 4430'

Comm: 11-20-59
Comp: 12-4-59

Casing:

8-5/8" @ 283'

Cement:

with 200 sacks

FORMATION

DEPTH

Sand
Shale
Red Bed
Anhydrite
Shale & Shells
Lime & Shale
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Lime & Shale
Mississippi
Lime
Cherty-Lime
Viola
Simpson

150
370
973
1000
1825
2515
2700
3110
3196
3317
3436
3492
4162
4235
4270
4335
4365
4414
4430

Tops:

Anhydrite
Heetner
Toronto
Douglas
Brown Lime
Lans. K. C.
Conglomerate
Mississippi

973
3617
3636
3654
3665
3786
4138
4203

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and
correct to the best of my knowledge.

O. P. Honaker

Subscribed and sworn to before me this 7th day of December, 1959.

Leroy L. Lutz
Notary Public

My commission expires: 10-17-63

RECEIVED
STATE CONSERVATION COMMISSION
DEC 8 1959
CONSERVATION DIVISION
Wichita, Kansas