

15-185-11095-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 10 Twp. 25 Rge. (E) 15 (W)

Location as "NE/CNWxSWx" or footage from lines NW SE SW
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name IRMA SMITH Well No. 2
Office Address P. O. BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed SEPTEMBER 2 1961
Application for plugging filed NOVEMBER 2 1965
Application for plugging approved NOVEMBER 3 1965
Plugging commenced NOVEMBER 17 1965
Plugging completed MARCH 12 1966
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	NONE
				5 1/2"	4069'	2912.34

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4070' - 3900' - PLUG
3900' - 3865' - SAND
3865' - 3825' - 5 SACKS CEMENT
3825' - 250' - MUD
250' - 235' - ROCK BRIDGE
235' - 216' - 8 SACKS CEMENT
216' - 165' - 17 SACKS CEMENT
165' - 40' - MUD
40' - 30' - ROCK BRIDGE
30' - BASE - 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966

4-11-66
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P. O. BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*

P. O. BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25TH day of MARCH, 1966

My commission expires JULY 31, 1966 *Mary M. Sweeney* Notary Public.

15-185-11095-0000

CONTINENTAL OIL COMPANY - Operator

SIERRA PETRO. CO., INC. - Contractor

IRMA SMITH #2
NW 37 SW
Sec. 10-25B-154
Stafford County, Kansas

T. D.: 4070'

Commenced: 8-21-61
Completed: 9-2-61

Casing:

Cement:

8-5/8" Set at 262'
5-1/2" Set at 3769'
4069'

with 225 ex. cement
with 300 ex. cement

FORMATION

DEPTH

Sand	175
Shale	274
Red Bed	947
Anhydrite	966
Shale & Shells	1350
Salt & Shale	1500
Shale & Shells	1843
Shale & Lime	2645
Lime	2757
Shale & Lime	3582
Lime	3628
Lime & Shale	3750
Lime	4070

TOPS:

Keelmer
Brown Lime
Lansing Kansas City

4070 RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966
3-11-66
OBSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSWELL)

I hereby certify that the above information is true
and correct to the best of my knowledge.

C. T. Hansen

Subscribed and sworn to before me this 5th day of September,
1961.

Leroy Drey
Notary Public

My commission expires: 10-17-63

STATE CORP COMM.
Kans. Geological Society
HM
ORW
File

RECEIVED	
SEP 12 1961	
KANSAS PRODUCTION	
NOTE	NOTED
DS	✓
DAC	✓
DE	
SPE	
PE	<i>[Signature]</i>
SA-A	
SA-B	
SA-C	

b