


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-185-19082-0000  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 10 Twp 25S Rge. 15 (X) (W)  
Location as "NE/CNWxSWx" or footage from lines 1650' f S, 990' f W  
Lease Owner Continental Oil Company  
Lease Name Irma I. Smith Well No. 3  
Office Address Box 30, Lyons, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 18, 19 61  
Application for plugging filed September 18, 19 61  
Application for plugging approved September 18, 19 61  
Plugging commenced September 18, 19 61  
Plugging completed September 18, 19 61  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4270 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	266'	8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Using drill pipe, spotted 15 sacks of cement at 4270'; filled hole with mud to 240'; spotted 1/4 sack of hulls and 25 sacks of cement; filled hole with mud and completed plugging with 1/4 sack of hulls and 10 sacks of cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1961  
CONSERVATION DIVISION  
Wichita, Kansas

9-27-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sierra Petroleum Company, Inc.  
Address 208 Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
W. S. Akers (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 30, Lyons, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 61

My commission expires May 5, 1965

Notary Public.

DBB-EJH  
9-25-61

24-2675-S 2-52-20M



State Corporation Commission  
CRW File F. W. Hampel, Pretty Prairie, Kansas

15-185-19082-0000

CONTINENTAL OIL COMPANY - Operator

SIERRA PETRO. CO., INC - Contr.

IRMA SMITH #3  
SE NW SW  
Sec. 10-25S-15W  
Stafford County, Kansas

T. D.: 4270'  
Elev.: 2037' K.B.

Commenced: 9-4-61  
Completed: 9-18-61

Casing: 8-5/8" Set at 267'  
Cement: with 225 sx. Common

FORMATION	DEPTH
Sand	185
Shale	268
Red Bed	974
Anhydrite	990
Shale & Shells	1350
Shale & Salt	1570
Shale & Shells	1855
Lime & Shale	3349
Lime	3442
Lime & Shale	3530
Lime	3727
Lime & Shale	3780
Lime	4221
Mississippi & Kinderhook	4238
Kinderhook	4270

TOPS

Anhydrite

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1961

CONSERVATION DIVISION  
Wichita, Kansas

974

9-20-61

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

C.T. Honaker

Subscribed and sworn to before me this 19th day of September,  
1961.

Jeroy Dietz  
Notary Public

My commission expires: 10-17-63