


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-185-11931-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

STAFFORD County, Sec. 10 Twp. 25S Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner CONTINENTAL OIL COMPANY
Lease Name IRMA SMITH Well No. 4
Office Address BOX 2197, HOUSTON, TEXAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed DECEMBER 2, 19 61
Application for plugging filed DECEMBER 3, 19 61
Application for plugging approved DECEMBER 3, 19 61
Plugging commenced DECEMBER 3, 19 61
Plugging completed DECEMBER 3, 19 61
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, ST. JOHN, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4272 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand & Shale</u>	<u>Surface Csg.</u>	<u>-0-</u>	<u>267'</u>	<u>8-5/8"</u>	<u>267'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: FILLED WITH HEAVY MUD 4272' UP TO 240', 1/3 SK. HULLS, HALLIBURTON PLUG, 40 SX. CEMENT THROUGH DRILL PIPE BY HALLIBURTON. FILLED HOLE WITH MUD TO 35', 1/2 SK. HULLS, HALLIBURTON PLUG, 10 SX. CEMENT TO CELLAR -0-.

JOB COMPLETED: 3 P.M. 12-3-61.

STATE CORPORATION COMMISSION
WICHITA, KANSAS

DEC 6 1961

CONSERVATION DIVISION
WICHITA, KANSAS

12-6-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.T. Honaker C. T. HONAKER, DRUG. SUPT.

BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 5TH day of DECEMBER, 19 61

My commission expires 10-17-63

Jersey Siet
Notary Public



15-185-11931-0000

CONTINENTAL OIL COMPANY - Operator
SIERRA PETROLEUM CO., INC. Contractor

T.D.: 4272'
Elev: 2038' K.B.

IRMA SMITH #4
SE SE SW
Sec. 10-25S-15W
Stafford County, Kansas

Commenced: 11-21-61
Completed: 12-2-61

Casing:
8-5/8" Set at 267'

Cement:
with 225 sx. cement

FORMATION	DEPTH
Sand	190
Shale	330
Red Bed	972
Anhydrite	995
Shale & Shells	1340
Shale & Salt	1550
Shale & Shells	1850
Lime & Shale	3760
Lime	4238
Mississippi	4272

RECORDED
STATE CORPORATION COMMISSION
DEC 6 1961
CONSERVATION DIVISION
TOPEKA, KANSAS
12-6-61

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true
and correct to the best of my knowledge.

C.T. Honaker

Subscribed and sworn to before me this 5th day of December,
1961.

Leroy Dicy
Notary Public

My commission expires: 10-17-63