


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-185-01492-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 35 Twp. 25 Rge. (E) 14 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SW NE SW
Lease Owner Musgrove Petroleum Corporation
Lease Name GARNER Well No. 1
Office Address 801 Union Center, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 16, 19 58
Application for plugging filed verbally August 15, 19 58
Application for plugging approved verbally August 15, 19 58
Plugging commenced August 16, 19 58
Plugging completed August 16, 19 58
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	339'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240'.
Set 1st Plug at 240' with 1/2 sk hulls & 20 sx cement.
Filled hole with heavy mud to 35'.
Set 2nd Plug at 35' with 1/2 sk hulls & 10 sx cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick
I, Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1958

My commission expires June 16, 1959.

Leah Joyce Neff
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

8-21-58

PLUGGING
FILE SEC 35 T. 25 R. 14 W
BOOK PAGE 125 LINE 5

AUG 21 1958
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: GARNER #1
 LOCATION: SW NE SW, Sec. 35-25-14W
 Stafford County, Kansas
 COMMENCED: July 30, 1958
 COMPLETED: August 16, 1958

o.	185	Sand & Shale
	185	Red bed & shale
	370	Shale & shells
	875	Lime & shale
	930	Shale & shells
	1230	Lime & shale
	3450	Lime
	3540	Lime & shale
	3880	Lime
	4234	Cherty Lime
	4269	Lime, shale & chert
	4331	Lime & chert
	4385	Lime, sand, shale
	4442	Lime & shale
	4480	Lime
	4510	Rotary Total Depth

Set 8-5/8" surface casing at 339' with 275 sx Sunset Cement.

Dry & abandoned

ELEVATION:	1982' Gr.	TOPS:	Sample	Schlumberger
	1985' D. F.	Heebner	3610'	3607' (-1620)
	1987' K. B.	Douglas	3650'	3648' (-1661)
		Brown Lime	3761'	3761' (-1774)
		Lansing	3793'	3790' (-1803)
		Miss.	4189'	4189' (-2202)
		Viola	4282'	4310' (-2323)
		Simpson	4387'	4388' (-2401)
		Arbuckle	4465'	4459' (-2472)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, EMIL E. BOWERS, do hereby certify that the above and foregoing is a true and correct copy of the log of the GARNER #1, SW NE SW, Section 35-25-14W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Emil E. Bowers
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of August, 1958.

8-21-58

Leah Joyce Neff RECEIVED
 Notary Public STATE CORPORATION COMMISSION

My commission expires June 16, 1959

PLUGGING		AUG 21 1958
FILE	SEC 35 T 25 R 14W	VATION DIVISION
BOOK	PAGE 125 LINE 5	2. Kansas