

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-20,991-0000

LEASE NAME Cudney A

WELL NUMBER 8

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

1216 Ft. from S (N) Line of Section (circle one)

1656 Ft. from E (W) Line of Section (circle one)

LEASE OPERATOR FG Hall Co. LLC

SPOT LOCATION Irregular Section

ADDRESS 6427 E. Kellogg Box 780167

SEC. 4 TWP. 26 S. RGE 16 (E) or (W)

CITY, STATE, ZIP Wichita, Ks. 67218-6167

COUNTY Edwards

PHONE# 316 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed _____

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 4-3-95

Date Plugging Completed ~~4-3-95~~ 4-26-95

The plugging proposal was approved on 5-1-95 (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes. If not, is well log attached? _____

Producing Formation(s) _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	438	8 5/8	438	0
		0	4565	4 1/2	4565	2340 ft.

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

3 hulls - 10 gel - 50 sx. cement - 10 gel - 1 hulls - 8 5/8 plug - 150 sx. cement. 60-40 poz 6% gel. 400# max 50# S.I.P.
Top of cement 140 ft. from surface - filled to top with redi-mix. Well was sanded 50' above top perms + 4sx. cement on top.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

RECEIVED
 KANSAS CORPORATION COMMISSION

License No. 5893

MAY 26 1995

Address P.O. Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: FG Hall Co. LLC


STATE OF Kansas COUNTY OF Pratt, ss.

CONSERVATION DIVISION
 WICHITA, KS

Judy Berry (Employee of Operator or Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry



(Address) 90 P.W.S., Inc.

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1995

Dorothy M. Ferguson
 Notary Public

My Commission Expires: 02/06/97