

15-047-21007-0000
~~20689~~

WELL PLUGGING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Feb 10

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 4 TWP. 26E R16W E/W
 Location as in quarters or footage from lines:
1876' FNL; 1656' FWL, NW/4 CONSERVATION DIVISION
 Wichita, Kansas

Lease Owner Sterling Drilling Company
 Lease Name Mayhew "A" 10-4 Well No. 10-4
 Office Address P. O. Box 129, Sterling, Kansas 67579
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed February 9, 1982
 Application for plugging filed February 9, 1982
 Plugging commenced 7:00 AM, February 9, 1982
 Plugging completed 9:00 AM, February 9, 1982
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation Depth to top bottom T.D. 4570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	423'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from
 feet to feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 1020' with 50 sacks through open ended drill pipe
at 1020'; heavy mud to 400' with 35 sacks through open ended
drill pipe at 400'; heavy mud to 40' with Howco plug, 1/2
sack hulls with solid bridge at 40', 10 sacks to surface and
10 sacks in rathole. Used Regular cement with 2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) [Signature]
F. A. Wuellner, Secretary
 (Address)
P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 82.



[Signature]
 Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - MAYHEW "A" 10-4
Located: 1876' FNL; 1656' FWL, NW/4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 2, 1982
COMPLETED: February 9, 1982

TOTAL DEPTH: 4570'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 164 Sand	Ran 10 joints new 8 5/8" OD 24# new casing.
164 - 425 Sand and Shale	410.38' pipe set at 423 K.B. Cemented with
425 - 1071 Shale	375 sacks 60/40 Pozmix with 2% gel and 3% cc.
1071 - 1085 Anhydrite	Plug down at 9:45 PM, 2-2-82, by Howco.
1085 - 1115 Shale	
1115 - 3855 Lime and Shale	
3855 - 4030 Lime	
4030 - 4385 Lime and Shale	
4385 - 4570 Lime	Plugged.

Deviation Surveys: 1 1/4° at 2077'
1 3/4° at 4570'