

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Edwards County, Sec 23 Twp 26S Rge 18 (E) 18 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines C-SW-SE The Carter Oil Company Ben Bordewick Well No. 1 Box 786 - Great Bend, Kansas Dry Hole 7-29-55 19 7-29-55 19 8-1-55 19 8-1-55 19 8-1-55 19 dry hole

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives Producing formation Depth to top Bottom Total Depth of Well 4795 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8-5/8", 354' 6", -0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud 4795' to 300' 8-5/8" Howco plug 300' " 299' 30 sx cement 299' " 209' Mud 209' " 60' 8-5/8" Howco plug 60' " 59' 20sx cement 59' " -0-

RECEIVED STATE CORPORATION COMMISSION AUG 11 1955 CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Carter Oil Company Box 786 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss. Hugh H. Goerner (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hugh H. Goerner Box 786, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10th day of August, 19 55

My commission expires May 4, 1957

Val Peterson Notary Public, Barton County, Kansas.

PLUGGING FILE SEC 23 T 26 R 18W BOOK PAGE 132 LINE 12

DRILLERS LOG

15-047-60293-0000

Operator- Carter Oil Company,  
 Lease Ben Bordewick Estate No. 1  
 Location- Cen. SW SE Sec. 23-26S-18W. Edwards County, Kansas.  
 Contractor- Adkins Drilling Company, Inc. Great Bend, Kansas.

Formation	From	To	Formation	From	To
Sand	0	60			
Sand	60	248			
Sand & Shale	248	373			

Sec. 11 joints (352.52ft) 8 5/8"  
 Casing set at 359 ft. Cemented with  
 300 sacks of Posmex Cement.

Shale	373	1550
Shale & Shells	1550	1914
Shale & Lime	1914	2340
Sand & Shale	2340	2429
Sand & Lime	2429	2548
Lime & Shale	2548	2941
Shale & Lime	2941	3539
Sandy Shale & Lime	3539	3663
Lime & Shale	3663	3848
Shale & Lime	3848	3938
Lime & Shale	3938	4121
Lime-shale & Sand	4121	4171
Lime & Shale	4171	4286
Lime	4286	4403
Lime & Shale	4403	4527
Lime	4527	4546
Shale-sand & chert	4546	4585
Shale & Chert	4585	4608
Chert-shale & dolomite	4608	4686
Sand & Dolomite	4686	4767
Lime	4767	4795

Total Depth 4795

Well Dry and ~~abandoned~~ Plugged.

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF BARTON )

Jim Adkins, of lawful age deposes and says that he is President of Adkins Drilling Company, Inc. and that the foregoing is a true and correct copy of Drillers Log of Ben Bordewick Estate No. 1. to the best of his knowledge.

Subscribed and sworn to before me this 1st day of August 1955.

Jim Adkins  
 \_\_\_\_\_  
Lawrence B. Adkins  
 \_\_\_\_\_  
 Notary Public.

My Commission expires  
2-29-1956.

**PLUGGING**  
 FILE SEC 23 T. 26 S. 18 W.  
 BOOK PAGE 139 LINE 12