

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-047-20534-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 29 Twp. 26S Rge. 18W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW SE

Lease Owner Alpine Drilling Co., Inc.
Lease Name Gamble Well No. 1
Office Address 800 Bitting Bldg., Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole



Locate well correctly on above
Section Plot

Date Well completed August 11 19 79
Application for plugging filed August 11 19 79
Application for plugging approved August 11 19 79
Plugging commenced August 10 19 79
Plugging completed August 11 19 79
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. Owen, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4840
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged as follows:

50 sx at 600'; 40sx at 300'; 12 sx - 1/2 sx hulls & plug at 40';
3 sx in rat hole; 1sx water well 50/50 poz mix cement w/6% gel
by Allied; Plugged 1 a.m. 8-11-79;
State Plugger; Wm. Owen, Pratt, Kansas
Walt Coldwater, Ellinwood, Kansas 67526


RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HUSKY DRILLING CO., INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Bldg., Wichita, Kansas 67202
(Address)



TO before me this day of August, 1979
Vickie O. Burris Notary Public.

My commission expires March 30, 1982



800 Biting Bldg
 Wichita, Kansas 67202
 Phone 316 - 263-7904
 Mobile Phone 316 - 793-7859 Unit 7070

15-047-20534-0000

August 13, 1979

WELL LOG- - - - -Gamble No. 1
 Located: NW SW SE of Sec. 29-26S-18W, Edwards Co., Kansas

OWNER: Alpine Drilling Co., Inc.
 ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: August 3, 1979
 COMPLETED: August 10, 1979

Rotary Total Depth: 4840'

LOG

0 - 41 Surface soil & sand
 41 - 180 Sand
 180 - 310 Sand & clay
 310 - 525 Shale
 525 - 891 Shale & sand
 891 - 1246 Red Bed & shale
 1246 - 1275 Anhydrite
 1275 - 2114 Shale & shells
 2114 - 4187 Shale & lime
 4187 - 4485 Lime
 4485 - 4706 Lime & shale
 4706 - 4800 Lime & chert
 4800 - 4840 Lime & shale

CASING RECORD

Spud surface hole @ 2:55 p.m. - 8-3-79
 cut 310' - set at 306' w/275 sx by
 Allied.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 14 1979
 CONSERVATION DIVISION
 Wichita, Kansas

Plugged @ 1 a.m. 8-11-79 by Allied.