


15-047-00260-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County. Sec. 3 Twp. 26S Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines G-SW-SW-NW
Lease Owner J. M. Huber Corporation
Lease Name Bidleman Well No. 1
Office Address Box 978 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 4 1962
Application for plugging filed September 4 1962
Application for plugging approved September 4 1962
Plugging commenced September 4 1962
Plugging completed September 4 12:00 P.M. 1962
Reason for abandonment of well or producing formation Dry hole



If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. LaKamp
Producing formation None Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	324	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 300'
Put 25 sx cement at 300'
Filled w/mud to 35'
Put 10 sx on top
Put 2 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
Floyd L. Meade (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd L. Meade
Box 978 Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Sept, 1962

Arthur E. Meade
Notary Public.

My commission expires



J. M. HUBER CORPORATION
Biddleman No. 1
C-SW-SW-NW
Sec. 3-26S-19W
Edwards County, Kansas

15-047-00760-0000

W E L L L O G

<u>FROM</u>	<u>-</u>	<u>TO</u>	<u>FORMATION</u>
0	-	265	Surface soil sand shale
265	-	550	Shale
550	-	1,075	Red Bed and Shale 8-5/8" set @ 324'
1,075	-	1,625	Shale and Shells
1,625	-	2,310	Shale
2,310	-	2,550	Lime
2,550	-	4,222	Lime and Shale
4,222	-	4,865	Lime
4,865	-	4,882	Sand
4,882	-	4,932	Lime
		4,932	R T D

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1962

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas, County of Seward

I, Floyd L. Meade, do hereby certify that the foregoing is true and correct to the best of my knowledge and belief.

Floyd L. Meade
Floyd L. Meade

Subscribed and sworn to before me this 15th day of November, 1962.

Lydial M. Woods
Notary Public

My commission expires; August 5, 1964